

ORANGE RIVER BASIN

WHITING, MAINE

**ROCKY LAKE DAMS
ME - 00399**

**PHASE I INSPECTION REPORT
NATIONAL DAM INSPECTION PROGRAM**

The original hardcopy version of this report
contains color photographs and/or drawings.
For additional information on this report
please email



U.S. Army Corps of Engineers
New England District
Email: Library@nae02.usace.army.mil

**DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
WALTHAM, MASS. 02154**

MARCH 1979

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

7-7-102

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER ME 00399	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Rocky Lake Dams NATIONAL PROGRAM FOR INSPECTION OF NON-FEDERAL DAMS		5. TYPE OF REPORT & PERIOD COVERED INSPECTION REPORT
7. AUTHOR(s) U.S. ARMY CORPS OF ENGINEERS NEW ENGLAND DIVISION		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS		8. CONTRACT OR GRANT NUMBER(s)
11. CONTROLLING OFFICE NAME AND ADDRESS DEPT. OF THE ARMY, CORPS OF ENGINEERS NEW ENGLAND DIVISION, NEDED 424 TRAPELO ROAD, WALTHAM, MA. 02254		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE March 1979
		13. NUMBER OF PAGES 58
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) APPROVAL FOR PUBLIC RELEASE: DISTRIBUTION UNLIMITED		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES Cover program reads: Phase I Inspection Report, National Dam Inspection Program; however, the official title of the program is: National Program for Inspection of Non-Federal Dams; use cover date for date of report.		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) DAMS, INSPECTION, DAM SAFETY, Orange River Basin Whiting Maine Rocky Lake		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The dams consist of two stone filled timber crib structures located about 400 ft. apart. The dams are assessed to be in poor condition. Because the south-erly dam has been breached, it poses no threat to life or property downstream. It is intermediate in size with a hazard potential of low.		

TC557
•M2
ME 399

Rocky Lake Dams, Whiting, Maine: phase
I inspection report, National Dam
Inspection Program. -- Waltham, Mass:
: U.S. Army Corps of Engineers, New
England Division, 1979.
vi, [58] p. : ill., maps ; 28 cm. --
(ME00399)
"March 1979"

1. Dams--Inspection--Maine--Rocky
Lake Dams. 2. Dam safety--Maine--Rocky
Lake Dams. 3. Rocky Lake Dams (Me.)--
Inspection. 4. Whiting (Me.)--Dams.
5. Orange River watershed (Me.)--Dams.
I. United States. Army. Corps of
Engineers. New England Division.
II. Series

29 OCT 86 14562973 AEEMsl



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02154

REPLY TO
ATTENTION OF:
NEDED

MAY 29 1979

Honorable Joseph E. Brennan
Governor of the State of Maine
State Capitol
Augusta, Maine 04330

Dear Governor Brennan:


I am forwarding to you a copy of the Rocky Lake Dams Phase I Inspection Report, which was prepared under the National Program for Inspection of Non-Federal Dams. This report is presented for your use and is based upon a visual inspection, a review of the past performance and a brief hydrological study of the dam. A brief assessment is included at the beginning of the report. I have approved the report and support the findings and recommendations described in Section 7 and ask that you keep me informed of the actions taken to implement them. This follow-up action is a vitally important part of this program.

A copy of this report has been forwarded to the Department of Agriculture and the Department of Transportation, cooperating agencies for the State of Maine. In addition, a copy of the report has also been furnished the owner, M.J. Garber and Herman Galvin, c/o Mr. Warren Strout, MacDonald Page Co., 562 Congress Street, Portland, Maine 04112.

Copies of this report will be made available to the public, upon request, by this office under the Freedom of Information Act. In the case of this report the release date will be thirty days from the date of this letter.

I wish to take this opportunity to thank you, the Department of Agriculture and the Department of Transportation for your cooperation in carrying out this program.

Sincerely yours,


JOHN P. CHANDLER
Colonel, Corps of Engineers
Division Engineer

Incl
As stated

ORANGE RIVER BASIN

WHITING, MAINE

ROCKY LAKE DAMS

ME-00399

PHASE I INSPECTION REPORT

NATIONAL DAM INSPECTION PROGRAM

NATIONAL DAM INSPECTION PROGRAM

PHASE I INSPECTION REPORT

ME-00399

ROCKY LAKE DAMS

WASHINGTON COUNTY, MAINE

ROCKY LAKE

November 28, 1978

BRIEF ASSESSMENT


The Rocky Lake Dams consists of two stone-filled timber crib structures located about 400 feet apart, separated by an island. The northerly dam is in seriously dilapidated condition and the southerly dam has been breached and retains no water. The northerly dam is about 14 feet high, and is about 150 feet long.

Based on the visual inspection, the Rocky Lake Dams are assessed to be in poor condition. Because the southerly dam has been breached, it poses no threat to life or property downstream. Although the northerly dam is in poor condition, the structure appears to present little threat to the safety of downstream residents or property. Based on the Corps of Engineers guidelines, the dams are classified as intermediate size dams having a low hazard potential.


The spillway test flood is one-half the probable maximum flood (PMF). The test flood outflow is about 1450 cfs. The spillway capacity of the northerly dam plus capacity of the culvert under the road, located about 100 feet downstream of the breached southerly dam, is about 59 percent of the routed test flood.

Due to the dilapidated condition of both dams, it appears that an attempt to repair the structures would be impractical. Complete reconstruction would be required to upgrade the condition of the structures. Within 12 months of receipt of this report, the Owner should engage a qualified engineer to advise him whether to remove or reconstruct the


dams. Reconstruction or removal should be done under the supervision of a qualified engineer. If the dams are to be reconstructed, a program of annual periodic technical inspection should be instituted.





EDWARD C. JORDAN CO., INC.


Stanley E. Walker, P.E.
Project Officer


This Phase I Inspection Report on Rocky Lake Dam has been reviewed by the undersigned Review Board members. In our opinion, the reported findings, conclusions, and recommendations are consistent with the Recommended Guidelines for Safety Inspection of Dams, and with good engineering judgment and practice, and is hereby submitted for approval.


JOSEPH W. FINEGAN, JR., MEMBER
Water Control Branch
Engineering Division


CARNEY M. TERZIAN, MEMBER
Design Branch
Engineering Division


JOSEPH A. MCELROY, CHAIRMAN
Chief, NED Materials Testing Lab.
Foundations & Materials Branch
Engineering Division

APPROVAL RECOMMENDED:


JOE B. FRYAR
Chief, Engineering Division

PREFACE

This report is prepared under guidance contained in the Recommended Guidelines for Safety Inspection of Dams, for Phase I investigations. Copies of these guidelines may be obtained from the Office of Chief of Engineers, Washington, D.C. 20314. The purpose of a Phase I investigation is to identify expeditiously those dams which may pose hazards to human life or property. The assessment of the general condition of the dam is based upon available data and visual inspections. Detailed investigation, and analyses involving topographic mapping, subsurface investigations, testing, and detailed computational evaluations are beyond the scope of a Phase I investigation; however, the investigation is intended to identify any need for such studies.

In reviewing this report, it should be realized that the reported condition of the dam is based on observations of field conditions at the time of inspection along with data available to the inspection team. In cases where the reservoir was lowered or drained prior to inspection, such action, while improving the stability and safety of the dam, removes the normal load on the structure and may obscure certain conditions which might otherwise be detectable if inspected under the normal operating environment of the structure.

It is important to note that the condition of a dam depends on numerous and constantly changing internal and external conditions, and is evolutionary in nature. It would be incorrect to assume that the present condition of the dam will continue to represent the condition of the dam at some point in the future. Only through continued care and inspection can there be any chance that unsafe conditions be detected.

Phase I inspections are not intended to provide detailed hydrologic and hydraulic analyses. In accordance with the established guidelines, the spillway test flood is based on the estimated "Probable Maximum Flood" for the region (greatest reasonable possible storm runoff), or fractions thereof. Because of the magnitude and rarity of such a storm event, a finding that a spillway will not pass the test flood should not be interpreted as necessarily posing a highly inadequate condition. The test flood provides a measure of relative spillway capacity and serves as an aide in determining the need for more detailed hydrologic and hydraulic studies, considering the size of the dam, its general condition and the downstream damage potential.

TABLE OF CONTENTS

	<u>PAGE</u>
LETTER OF TRANSMITTAL	
BRIEF ASSESSMENT.....	i
REVIEW BOARD SIGNATURE SHEET.....	iii
PREFACE.....	iv
TABLE OF CONTENTS.....	v
OVERVIEW PHOTOGRAPH.....	vii
LOCATION AND DRAINAGE MAP.....	viii

SECTION 1 - PROJECT INFORMATION

1.1 GENERAL.....	1-1
1.2 DESCRIPTION OF PROJECT.....	1-1
1.3 PERTINENT DATA.....	1-3

SECTION 2 - ENGINEERING DATA

2.1 DESIGN.....	2-1
2.2 CONSTRUCTION.....	2-1
2.3 OPERATION.....	2-1
2.4 EVALUATION.....	2-1

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS.....	3-1
3.2 EVALUATION.....	3-2

SECTION 4 - OPERATING PROCEDURES

4.1 PROCEDURES.....	4-1
4.2 MAINTENANCE OF DAM.....	4-1
4.3 MAINTENANCE OF OPERATING FACILITIES.....	4-1
4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT.....	4-1
4.5 EVALUATION.....	4-1

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES.....	5-1
---------------------------------	-----

TABLE OF CONTENTS (Continued)

SECTION 6 - STRUCTURAL STABILITY


6.1 EVALUATION OF STRUCTURAL STABILITY.....	6-1
---------------------------------------------	-----

SECTION 7 - ASSESSMENT, RECOMMENDATIONS AND REMEDIAL MEASURES

7.1 DAM ASSESSMENT.....	7-1
7.2 RECOMMENDATIONS.....	7-1
7.3 REMEDIAL MEASURES.....	7-2
7.4 ALTERNATIVES.....	7-2


APPENDICES

A FIELD INSPECTION NOTES	
B ENGINEERING DATA	
C PHOTOGRAPHS	
D HYDROLOGIC AND HYDRAULIC COMPUTATIONS	
E INVENTORY FORMS	



OVERVIEW

ROCKY LAKE DAMS WATERSHED BOUNDARY



U.S. GEOLOGICAL SURVEY MAP
GARDNER LAKE, ME. QUADRANGLE
EASTPORT, ME. QUADRANGLE

0 1 2 3 MILES

EDWARD C. JORDAN CO., INC. PORTLAND, MAINE	U.S. ARMY ENGINEER DIV NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	
ROCKY LAKE DAMS	
LOCATION & DRAINAGE AREA MAP	
ROCKY LAKE	ME.
2079915	SCALE AS SHOWN DATE MARCH 1979

PHASE I INSPECTION REPORT

ROCKY LAKE DAMS

SECTION 1

PROJECT INFORMATION

1.1 GENERAL

a. Authority. Public Law 92-367, August 8, 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a National Program of dam inspection throughout the United States. The New England Division of the Corps of Engineers has been assigned the responsibility of supervising the inspection of dams within the New England Region. Edward C. Jordan Co., Inc. has been retained by the New England Division to inspect and report on selected dams in the states of Maine and New Hampshire. Authorization and notice to proceed were issued to Edward C. Jordan Co., Inc. under a letter of December 1, 1978 from Max B. Scheider, Colonel, Corps of Engineers. Contract No. DACW33-79-C-0017 has been assigned by the Corps of Engineers for this work.

b. Purpose

- (1) To perform technical inspection and evaluation of non-Federal dams to identify conditions which threaten the public safety and thus permit correction in a timely manner by non-Federal interests.
- (2) To encourage and prepare the states to initiate quickly effective dam safety programs for non-Federal dams.
- (3) To update, verify and complete the National Inventory of Dams.

1.2 DESCRIPTION OF PROJECT

a. Location. The Rocky Lake Dams are located at the outlet of Rocky Lake in the town of Whiting, Maine. N 44°-46.1', W 67°-16.0'.

- b. Description of Dam and Appurtenances. The Rocky Lake Dams consist of two stone-filled timber crib structures located about 400 feet apart and separated by an island. The northerly dam is in seriously deteriorated condition and the southerly dam has been breached and retains no water. The northerly dam is about 14 feet high and is about 150 feet long.

Plan and profile and cross-sections are presented in Appendix B.

- c. Size Classification. The Rocky Lake Dams have a storage capacity of about 9000 acre-feet and a height of 14 feet. According to Corp of Engineer's "Recommended Guidelines for Safety Inspection of Dams," a dam with storage capacity greater than 1,000 acre-feet but less than 50,000 acre-feet or a height greater than 40 feet but less than 100 feet is classified as an intermediate size dam.

- d. Hazard Classification. The Rocky Lake Dams are classified as having a low hazard potential. The peak flow from the hypothetical failure of the dams was estimated to be about 6900 cfs based on guideline procedures provided by the Corps of Engineers. Failure of the dams would result in water surface elevations about 6.5 feet higher than normal at the outlet of Orange Lake and about 7 feet higher than normal at the first downstream bridge, about 2.2 miles below the dam. Downstream of this bridge the water surface elevation would essentially be retained within swampy areas located in the flood plain.

- e. Ownership.

Current Co-Owners: M.J. Garber & Herman Galvin
Contact: M.J. Garber
c/o Warren Strout
MacDonald Page Co.
562 Congress Street
Portland, Maine 04112
Tel. 207-774-5701

Previous Owner: Unknown

f. Operator.

None. (See e. above for contact person.)

g. Purpose of Dam. This dam is presently used to control the water level at Rocky Lake Dam for recreational purposes.

h. Design and Construction History. There is no available design and construction data pertinent to the dams.

i. Normal Operating Procedure. No operating and maintenance program is followed.

1.3 PERTINENT DATA

a. Drainage Areas. The drainage area consists of approximately 16.8 square miles of gently sloping forested terrain. Rocky Lake has an area of 1.8 square miles (1150 acres), which represents about 11 percent of the drainage area.

b. Discharge at Damsite. No record of high water could be located. The impounding system consists of a northerly and a southerly dam separated by an island. The southerly dam has been breached and hydraulic control for flood waters is at the road culvert, about 100 feet downstream of the dam.

(1) Outlet Works - The outlet works at the northerly dam are inoperable. At the southerly dam (roadway hydraulic control), there is a culvert that measures 8.8 feet wide by 11.8 feet high with an invert elevation of 79 MSL, about 7.5 feet below the lake outlet. The capacity of the culvert flowing full is about 460 cfs.

(2) The maximum flood at the damsite is unknown.

(3) Ungated spillway capacity with the pond at the top of the northerly dam is 400 cfs. There is no spillway at the southerly dam.

(4) Gated spillway capacity is not applicable.

- (5) Total project discharge at test flood (1/2 PMF) elevation of 93 is 1450 cfs.

c. Elevation. The survey datum was adjusted to mean sea level (MSL) datum based on the assumption that spillway crest of the northerly dam is equal to normal water surface elevation of 90 (MSL), as shown on the Gardner Lake, Maine U.S. Geologic Survey quadrangle. Due to the breaching of the southerly dam, present normal water surface is assumed to be elevation 88 (MSL).

The following elevations above mean sea level are approximate only.

<u>Item</u>	<u>Elevation (Feet Above MSL)</u>
Top of northerly dam	92.0
Top of roadway downstream of southerly dam	93.7
Test flood (1/2 PMF) pool	93.0
North dam spillway crest	90.0
Full flood control pool	N/A
Recreation pool	88
Invert culvert located down- stream of southerly dam	78.9
Streambed at centerline of northerly dam	78
Maximum tailwater	Unknown

d. Reservoir.

<u>Item</u>	<u>Length (Miles)</u>
Maximum pool	3.8
Recreation pool	3.5
Flood control pool	N/A

e. Storage.

Item	Storage (Acre-Feet)
Recreation pool (elev. 88)	4200
Northerly dam spillway crest (elev. 90)	6510
Top of dam (elev. 92)	9320
Test flood (1/2 PMF) (elev. 93.0)	10430

f. Reservoir Surface.

Item	Surface Area (Acres)
Recreation pool	1100
Flood control pool	N/A
Spillway crest pool	1150
Test flood (1/2 PMF) pool	1465
Top of dam	1360

g. Dam.

Type - the dams are stone-filled timber crib structures abutted by earth embankments.

Length - The southerly dam has been breached; it was about 160 ft long. The length of the northerly dam is about 150 feet.

Height - The northerly dam is about 14 feet high.

Top Width - See plan and profile and cross-sections in Appendix B.

Side Slopes - See sketches in Appendix B.

Zoning - None.

Impervious Core - None.

Cutoff - Timber planking and mud seal.

Grout Curtain - None.

h. Diversion and Regulating Tunnel. Not applicable.

i. Spillway.

Type - The northerly dam has two self-loading timber deck spillways. See sketches in Appendix B.

Length - 39+ and 14+ feet.

Crest Elevation (Northerly Dam) - 90 (MSL).

Gates - None.

Downstream Channel - The channels below the northerly and southerly dams are narrow with a slope of about 0.7 percent. See Photographs 5 and 7. Both streambeds are composed primarily of gravel and cobbles. Located about 100 feet downstream of the southerly dam is an 8.8-foot wide by 11.8-foot high culvert beneath a road. This culvert appears to restrict the channel and is likely the hydraulic control during flood flow. The north channel is littered with debris, including two fallen trees. The two channels join as they enter Orange Lake about 1500 feet downstream of the dams.

j. Regulating Outlets.

Invert - Southerly dam - none
Northerly dam - 83 (MSL)

Size - Southerly dam - none
Northerly dam - two bays 5 ft wide by 9 ft high

Description - Control of the northerly dam outlet was by stop logs located between timber supports. Due to the deteriorated condition of the timber in the dam and the damming performed by beavers, the stop log outlet is not operable.

Control Mechanism - None

SECTION 2

ENGINEERING DATA

2.1 DESIGN

No design data were available for the Rocky Lake Dams.

2.2 CONSTRUCTION

No engineering data were available regarding construction of the dams.

2.3 OPERATION

No engineering operational data were available.

2.4 EVALUATION

- a. Availability. There are no engineering data or plans available that would be useful in evaluating the integrity of the Rocky Lake Dams.
- b. Adequacy. The lack of engineering data did not allow for a definitive review. Therefore, the adequacy of this dam could not be assessed from the standpoint of reviewing design and construction data, but is based primarily on visual inspection, performance history and engineering judgment.
- c. Validity. Not applicable.

SECTION 3
VISUAL INSPECTION

3.1 FINDINGS

- a. General. The Rocky Lake Dams consists of two structures which close the outlets from Rocky Lake. The structures are about 400 feet apart, separated by an island. The southerly dam has been breached and the northerly dam is in a dilapidated condition.
- b. Dams. The northerly dam is a stone-filled, timber cribwork structure. It is about 150 feet long and about 14 feet high. It is badly dilapidated as can be seen in Photograph 6. The timber members are rotted, split and broken, and many have become dislodged. The dam was retaining about 10 feet of water on November 28, 1978. Leakage through the structure was estimated to be 200 gpm. The stop log outlet works at the dam are dilapidated and inoperable and one outlet is presently closed by beaver workings.

The southerly dam was also a timber cribwork structure. It has been breached and presently retains no water. The timber structure is extremely dilapidated as shown in Photograph 5.

About 150 feet upstream of the remnants of the south dam, there is an earth embankment dike which appears to have been constructed since the breaching of the timber dam. This dike is about 200 feet long, 6 feet high and appears to close the old stream channel, as shown on the general site plan in Appendix B-1. The existing channel is just north of the northerly end of the dike. This channel has a bed consisting of bedrock overlain by cobbles and boulders. The channel is somewhat restricted by boulders and cobbles placed in the channel apparently to maintain low water hydraulic control. The earth dike appears to be in good condition. Some seepage is occurring at the downstream toe.

- c. Appurtenant Structures. Not applicable.

- d. Reservoir Area. The reservoir consists of Rocky Lake which is about 1150 acres and has a forested shoreline as shown in Photograph 3. There are a few cottages on the shore of the lake. The potential for slope failure above the dam appears minimal.
- e. Downstream Channel. The channels below the northerly and southerly dams are narrow with a slope of about 0.7 percent. See Photographs 5 and 7. Both streambeds are composed primarily of gravel and cobbles. Located about 100 feet downstream of the southerly dam is an 8.8-foot wide by 11.8-foot high culvert beneath a road. This culvert appears to restrict the channel and is likely the hydraulic control during flood flow. The north channel is littered with debris, including two fallen trees. The two channels join as they enter Orange Lake about 1500 feet downstream of the dams.

3.2 EVALUATION

Based on the visual inspection, the Rocky Lake Dams appears to be in poor condition. The northerly timber dam is badly dilapidated but presently intact and is retaining about 10 feet of water. The southerly timber dam has been breached. At the southerly dam low flow control is provided by a dike and restricted channel located about 150 feet upstream, and flood flows are controlled by the culvert beneath the road located about 100 feet downstream of the dam. Although in poor condition, the structure appears to present little threat to the safety of downstream residents or property. Further deterioration and eventual breaching will likely occur at the northerly dam. However, due to its timber cribwork construction, the breaching will likely occur in stages as opposed to a rapid failure of the entire structure.

SECTION 4
OPERATING PROCEDURES

4.1 PROCEDURES

There are no operating procedures.

4.2 MAINTENANCE OF DAM

There is apparently no maintenance program for the dams.

4.3 MAINTENANCE OF OPERATING FACILITIES

There is apparently no maintenance program for operating facilities.

4.4 DESCRIPTION OF ANY WARNING SYSTEM IN EFFECT

No warning system is known to be in effect.

4.5 EVALUATION

The Rocky Lake Dam operating equipment is in poor condition and is inoperable. No formal warning system for either high water or structural distress is in effect at the dams.

SECTION 5

HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

- a. General. Both the north and south dams are stone-filled timber crib structures. The south dam has been breached and the roadway just downstream serves as the flood water hydraulic control at the southerly damsite. The two dams are about 400 feet apart and are separated by an island.
- b. Design Data. Design data were not available.
- c. Experience Data. No information regarding specific overtopping events or other notable hydrologic occurrences was disclosed. However, it is reported by a local resident that the southerly dam breached about 10 years ago. The timbers on the northerly dam are rotted, split and broken, and many have become dislodged. However, the dam is still intact.
- d. Visual Observations. The outlet of Rocky Lake is controlled by two dams. The northerly dam outlet section is inoperable, and flow is controlled by two spillway sections. On November 28, 1978, the water surface of Rocky Lake was about 2 feet below spillway crest. About 150 feet upstream of the remnants of the breached southerly dam, there is an earth dike which reportedly has been constructed since the breaching of the timber dam. This dike is about 200 feet long, 6 feet high and appears to close the old stream channel. The existing channel is just north of the northerly end of the dike. This channel has a bed consisting of bedrock overlain by cobbles and boulders. The channel is somewhat restricted by boulders and cobbles placed about 2 feet high in the channel, apparently to maintain low water hydraulic control.

Below the breached southerly dam is a roadway culvert that provides flood water hydraulic control.

- e. Test Flood Analysis. The Rocky Lake Dams are classified as having a low hazard potential. Based on Corps of Engineers "Recommended Guidelines for

Safety Inspection of Dams" the spillway test flood is 1/2 of the probable maximum flood (PMF). The test flood was calculated to be about 5500 cfs, based on the COE's "Preliminary Guidance for Estimating Probable Maximum Discharges in Phase I Dam Safety Investigations." Consideration of the effect of surcharge storage reduces the test flood to 1450 cfs. The spillway capacity of the north dam plus the culvert capacity at the south damsite is about 860 cfs, which is about 59 percent of the routed 1/2 PMF. During the test flood event, the north dam would be overtopped by about 1 foot.

- f. Dam Failure Analysis. The hazard potential was determined by analyzing downstream dam failure hydrographs based on rule of thumb methods presented in an attachment to ETL 1100-2-234. The failure analysis assumes a breaching of the northerly dam with water surface at the top of the dam.

The peak flood flow including a breaching of the north dam, and flow through the culvert at the south damsite would be about 5700 cfs. Rocky Lake would empty in about 38 hours. The wave height at the north dam would be about 10 feet. At the outlet from Orange Lake, about 1.3 miles downstream, the flood peak would be attenuated to about 4200 cfs, and the normal elevation of the lake would rise about 6.5 feet. At the first downstream bridge, 2.2 miles below the dams, the flood peak would be reduced to about 3400 cfs and the flood depth would be about 7 feet. Downstream of the bridge the flood wave would essentially be maintained within swampy areas adjacent to the Orange River.

It appears that no downstream residences would be affected by failure of the dam. Potential damage appears to be limited to the cemetery on the north bank of the north discharge channel, and the bridge located about 2.2 miles downstream of the dams.

Since the timber crib structure of the north dam is badly dilapidated, resistance to overtopping is considered to be poor. Based on test flood calculations, the roadway at the south dam site would not be overtopped by the 1/2 PMF.

SECTION 6

STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

- a. Visual Observations. Based on the visual inspections, the Rocky Lake Dams appear to be in poor condition. The northerly timber dam is badly dilapidated but presently intact. However, flood flows overtopping the spillway sections would likely cause progressive breaching of the dam. Due to its timber cribwork construction, breaching will likely occur in stages. The southerly timber dam has been breached. The flow control at the south damsite is provided by a dike and restricted channel upstream and the road and culvert downstream.
- b. Design and Construction Data. None available.
- c. Operating Records. None available.
- d. Post Construction Changes. Since original construction, both the north and south dams have undergone progressive deterioration and the south dam has been breached. Subsequent to the breaching of the south dam, an earth dike had been constructed upstream of the timber dam to restrict the channel and maintain pond level.
- e. Seismic Stability. The dam is located in Seismic Zone No. 1 and in accordance with recommended Phase I Guidelines, does not warrant seismic analysis.

SECTION 7

ASSESSMENT, RECOMMENDATIONS, AND REMEDIAL MEASURES

7.1 DAM ASSESSMENT

- a. Condition. Based on the visual inspection and performance history of the Rocky Lake Dams, they are assessed to be in poor condition. The southerly dam has been breached. Low flow control is provided presently by an earth dike which restricts the upstream channel and, high flow control is provided by a roadway culvert in the downstream channel. The northerly dam is intact and retains about 10 feet of water. This timber structure is seriously dilapidated and flows overtopping the spillway section will likely cause progressive breaching. Due to the lack of significant downstream hazard, however, the condition presents little threat to the safety of downstream residents or property.
- b. Adequacy of Information. The information available is such that the assessment of the condition of the dam must be based primarily on the visual inspection, the past operational performance of the dam, and engineering judgment.
- c. Urgency. The recommendations and remedial measures outlined in 7.2 and 7.3 below should be implemented within 12 months after receipt of this report by the owner.
- d. Need for Additional Investigation. Additional investigation is not considered necessary for the current assessment.

7.2 RECOMMENDATIONS

A qualified engineer should be engaged to advise the Owner whether to remove or reconstruct the dams. Reconstruction or removal should be done under the supervision of a qualified engineer with consideration given to potential release of accumulated sediments or other possible environmental impacts of lowering the level of Rocky Lake. Any structure built to maintain the lake in back of the breached dam, such as the present dike, should be appropriately designed by a qualified engineer.

7.3 REMEDIAL MEASURES

- a. Operation and Maintenance Procedures. Due to their dilapidated condition, it appears that an attempt to repair the structures from their present condition would be impractical. Complete reconstruction would be required to upgrade the condition of the structures. If the dams are to be reconstructed, a program of annual periodic technical inspection should be instituted.

The remains of the south dam should be removed from the channel. Further break-up of this breached dam could clog the downstream culvert causing flooding.

7.4 ALTERNATIVES

The alternatives available appear to be removal of the structures or replacement (reconstruction) of the structures.

APPENDIX A

VISUAL INSPECTION CHECK LIST

AND

SUPPLEMENTARY INSPECTION NOTES

VISUAL INSPECTION CHECKLIST
PARTY ORGANIZATION

PROJECT Rocky Lake Dams

DATE 11/28/78

TIME P.M.

WEATHER Snow, rain, cold

W.S. ELEV. U.S. DN.S.

PARTY:

- | | |
|---------------------------|---------------------------------------------|
| 1. <u>Stephen Cole</u> | 6. <u> </u> |
| 2. <u>Brian Bisson</u> | 7. <u> </u> |
| 3. <u>Scott Decker</u> | 8. <u> </u> |
| 4. <u>John Kimble</u> | 9. <u> </u> |
| 5. <u>Charles Goodwin</u> | 10. <u> </u> |

PROJECT FEATURE	INSPECTED BY	REMARKS
1. <u>Geotechnical</u>	<u>Cole</u>	
2. <u>Structural</u>	<u>Cole, Decker</u>	
3. <u>Hydraulics/Hydrology</u>	<u>Bisson</u>	
4. <u>Civil</u>	<u>Decker</u>	
5. <u>Photography</u>	<u>Decker, Bisson</u>	
6. <u>Survey</u>	<u>Kimble, Goodwin</u>	
7. <u> </u>		
<u>Review Inspection</u>	<u>Stanley Walker and</u>	
<u>Dec. 14, 1978</u>	<u>Charles Horstmann</u>	
<u>No significant differences observed from 11/28/78 inspection</u>		

NOTE: See Supplementary Inspection Notes Following Checklist

INSPECTION CHECKLIST

PROJECT Rocky Lake Dams DATE 11/28/78
 PROJECT FEATURE Embankment NAME Cole
 DISCIPLINE Geotechnical NAME _____

AREA EVALUATED	CONDITIONS	
<u>DAM EMBANKMENT</u>	South dam dike* at pond, above old dam	North dam - no dike embankment
Crest Elevation	92+ (MSL)	
Current Pool Elevation	88 (MSL)	NOT APPLICABLE
Maximum Impoundment to Date	Unknown	
Surface Cracks	None	
Pavement Condition	Turf	
Movement or Settlement of Crest	None	
Lateral Movement	None	
Vertical Alignment	Okay	
Horizontal Alignment	Okay	
Condition at Abutment and at Concrete Structures	N/A	
Indications of Movement of Structural Items on Slopes	None	
Trespassing on Slopes	None	
Sloughing or Erosion of Slopes or Abutments	None	
Vegetation	Turf	

*Dike does not close the stream, about 40 feet of open channel exists north of the dike. This section controls at low flow.

AREA EVALUATED		CONDITIONS
<u>DAM EMBANKMENT</u> (cont.)	South Dam	North Dam
Rock Slope Protection - Riprap Failures	None	NOT APPLICABLE
Unusual Embankment or Downstream Seepage	Minor seepage near midpoint of dike.	
Piping or Boils	None	
Foundation Drainage Features	None	
Toe Drains	None	
Instrumentation System	None	

INSPECTION CHECKLIST

PROJECT Rocky Lake Dams DATE 11/28/78
 PROJECT FEATURE Intake Channel, Structural NAME Cole, Decker
 DISCIPLINE Structural, Geotechnical NAME Bisson
Hydraulics/Hydrology

AREA EVALUATED	CONDITION	
<u>OUTLET WORKS - INTAKE CHANNEL AND</u> <u>INTAKE STRUCTURE</u>	South Dam	North Dam
a. Approach Channel		
Slope Conditions	Flat, stable	Flat, stable
Bottom Conditions	Gravel	Ice covered, could not be observed.
Rock Slides or Falls	None	None
Log Boom	None	None
Debris	None	Beaver workings
Condition of Concrete Lining	N/A	N/A
Drains or Weep Holes	N/A	N/A
b. Intake Structure		
Condition of Concrete	N/A	Timber, poor
Stop Logs and Slots	N/A	Timber, poor

INSPECTION CHECKLIST

PROJECT Rocky Lake Dams

DATE 11/28/78

PROJECT FEATURE Control Tower

NAME Cole, Decker

DISCIPLINE Structural, Civil
Hydraulics/Hydrology

NAME Bisson

AREA EVALUATED	CONDITION	
<u>OUTLET WORKS - CONTROL TOWER</u>	South Dam	North Dam
a. Masonry and Structural		
General Condition	Old timber dam	Control tower con-
Condition of Joints	downstream of	sists of deteri-
Spalling	earth dike has	orated timber
Visible Reinforcing	been breached.	stop log bays.
Rusting or Staining of Concrete	Control tower has	
Any Seepage or Efflorescence	collapsed.	
Joint Alignment		
Unusual Seepage or Leaks in Gate Chamber		
Cracks		
Rusting or Corrosion of Steel		
b. Mechanical and Electrical		
Air Vents		Stop log bays are inoperable and filled with debris.
Float Wells	N/A	
Gate Hoist		
Elevator		

AREA EVALUATED	CONDITIONS	
<u>OUTLET WORKS - CONTROL TOWER (cont.)</u>	South Dam	North Dam
Hydraulic System	N/A	Stop log bays inoperable
Service Gates		
Emergency Gates		
Lightning Protection System		
Emergency Power System		
Wiring and Lighting System		

INSPECTION CHECKLIST

PROJECT Rocky Lake Dams DATE 11/28/78
 PROJECT FEATURE Transition, conduit NAME Cole, Bisson
 DISCIPLINE Structural, Civil NAME Decker
Hydraulics/Hydrology

AREA EVALUATED	CONDITION	
<u>OUTLET WORKS - TRANSITION AND CONDUIT</u>	South Dam	North Dam
General Condition of Concrete	Old timber dam	Deteriorated timber
Rust or Staining on Concrete	has been breached.	sill and training
Spalling		walls. Intact but
Erosion or Cavitation		badly rotted.
Cracking	NOT APPLICABLE	
Alignment of Monoliths		
Alignment of Joints		
Numbering of Monoliths		

PERIODIC INSPECTION CHECKLIST

PROJECT Rocky Lake Dams DATE 11/28/78
 PROJECT FEATURE Outlet Structure, Channel NAME Cole, Decker
 DISCIPLINE Structural, Geotechnical NAME Bisson
Hydraulics/Hydrology

AREA EVALUATED	CONDITION	
<u>OUTLET WORKS - OUTLET STRUCTURE AND OUTLET CHANNEL</u>	South Dam	North Dam
General Condition of Concrete	Old timber dam	Outlet structure
Rust or Staining	has been breached.	consists of timber
Spalling		cribwork, badly
Erosion or Cavitation		rotted.
Visible Reinforcing	NOT APPLICABLE	
Any Seepage or Efflorescence		
Condition at Joints		
Drain holes		
Channel		
Loose Rock or Trees Overhanging Channel	None	Trees in channel and on both sides of channel.
Condition of Discharge Channel	Bedrock, some cobbles and boulders. 8.8'x 11.8' culvert just below dam.	Channel bed consists of cobbles, gravel and boulders, no erosion evident.

INSPECTION CHECKLIST

PROJECT Rocky Lake Dams DATE 11/28/78
 PROJECT FEATURE Spillway NAME Cole, Decker
 DISCIPLINE Structural, Civil NAME Bisson
Hydraulics/Hydrology

AREA EVALUATED	CONDITION	
<hr/>		
<u>OUTLET WORKS - SPILLWAY WEIR, APPROACH AND DISCHARGE CHANNELS</u>	South Dam	North Dam
a. Approach Channel		
General Condition	Good	Good
Loose Rock Overhanging Channel	None	None
Trees Overhanging Channel	None	None
Floor of Approach Channel	Bedrock, gravel, cobble, boulders	Could not be ob- served, ice
b. Weir and Training Walls		
General Condition of Concrete and Masonry	Timber dam breached.	Timber cribwork, very rotten.
Rust or Staining		
Spalling	NOT APPLICABLE	
Any Visible Reinforcing		
Any Seepage or Efflorescence		
Drain Holes		
c. Discharge Channel		
General Condition		
Loose Rock Overhanging Channel	None	None
Trees Overhanging Channel	None	Trees in channel
Floor of Channel	Bedrock, cobble and boulders	Gravel, cobble and boulders
Other Obstructions	Culvert just down- stream	None

INSPECTION CHECKLIST

PROJECT Rocky Lake Dam DATE 11/28/78
 PROJECT FEATURE Service Bridge NAME Cole
 DISCIPLINE Structural NAME _____

AREA EVALUATED	CONDITION
----------------	-----------

OUTLET WORKS - SERVICE BRIDGE

a. Superstructure

Bearings

Anchor Bolts

Bridge Seat

Longitudinal Members

NOT APPLICABLE

Under Side of Deck

Secondary Bracing

Deck

Drainage System

Railings

Expansion Joints

Paint

b. Abutment & Piers

General Condition of Concrete

Alignment of Abutment

Approach to Bridge

Condition of Seat & Backwall

SUPPLEMENTARY INSPECTION NOTES

ROCKY LAKE DAMS WHITING, MAINE

APPENDIX A

The Rocky Lake Dams consists of two structures about 400 feet apart and separated by an island. The spillway section of the southerly dam has been breached. The breached width is approximately 20 feet and the stream is flowing in its natural streambed through this opening. The northerly dam was found to be retaining approximately 10 feet of water.

1. TIMBER STRUCTURES IN GENERAL

Both dams are constructed of stone-filled self-loading timber cribs. The timber members are seriously deteriorated and rotted. The broken timber members have become displaced and stone fill has fallen through. The penstock area and powerhouse at the southerly dam have collapsed and could not be inspected due to the hazardous condition of the dilapidated structure. The northerly dam, although seriously deteriorated is generally intact.

2. EMBANKMENT STRUCTURES

An earth embankment dike, located approximately 150 feet upstream of the southerly dam, partially closes the southerly outlet from Rocky Lake. This embankment is approximately 6 feet high with about an 8 foot top width and 2 to 1 side slopes. This embankment has a grassed surface and appears to be well maintained with little or no brush growth apparent. This embankment appears to have been constructed subsequent to the breaching of the dam downstream.

The embankment does not entirely close off the southerly outlet channel. It appears that the embankment was either not extended across the channel or has been breached. The channel is partially filled with stones and retains approximately 1 to 2 feet of water.

- a. Settlement. The southerly earthen embankment dike section was found to be in good condition with little or no settlement.

- b. Slope Stability. The slopes of the embankment appear generally true to line and grade and no slope stability problem appears to exist.
- c. Seepage. Very minor seepage was occurring at the downstream toe of this structure.
- d. Drainage Systems. None were observed.
- e. Slope Protection. Logs were lying on the upstream slope of the northerly dam, a little above the water line. No other form of slope protection was in evidence. Little or no erosion was apparent on the upstream slope.

3. SPILLWAY STRUCTURES

The spillway structure at the southerly dam has been breached. The northerly dam has a timber self-loading timber deck spillway. The timber is seriously deteriorated and in poor condition. There are no control gates on the spillway.

a. Control Gates and Operating Machinery.

None operable.

b. Unlined Saddle Spillways. The area north of the earth embankment dike upstream of the southerly dam is an unlined saddle spillway. It is about 40 feet in width, and consists of cobbles and boulders overlying bedrock.

c. Approach and Outlet Channels. Southerly dam approach appears to be clear and unobstructed both at the embankment dike upstream and at the breached dam. The southerly dam outlet channel is generally unobstructed, however, a 8.8 foot wide by 11.8 foot high culvert exists approximately 100 feet downstream from the dam. Debris from the old dam could plug this culvert during high flow conditions. The approach channel to the northerly dam was generally clear. However, a beaver lodge exists approximately 30 feet upstream of the dam near the north bank and debris from this area could clog the spillway or outlet sections of the dam structure. The outlet channel is lined with trees and could be easily obstructed by debris from the dam or debris passing over the dam.

d. Stilling Basin. The stilling basin at the southerly dam is a bedrock channel with no erosion apparent. The stilling basin at the northerly dam is a channel, no erosion was evident.

e. Drawdown Facilities. There are no drawdown facilities at either dam. Although the south dam has been breached, the lake outlet channel has been partially filled with stone to a height of about 2 feet, and at low flows the stone fill controls hydraulically. The north dam gates are inoperable.

4. OUTLET WORKS

There are no outlet works at the southerly dam. At the northerly dam there are two stop log outlet structures. One has been closed with vertical planking over the deteriorated stop logs. The other outlet has apparently been closed by debris and the work of beavers.

5. SAFETY AND PERFORMANCE INSTRUMENTATION

There is no safety performance instrumentation at the dam.

6. RESERVOIR

a. Shoreline. No major active or inactive landslide areas on the Rocky Lake shoreline were observed.

b. Sedimentation. The extent of sedimentation in the pond could not be observed during the visual inspection, but it does not appear to impede flow to either of the two dams.

c. Potential Upstream Hazard Area. No significant upstream hazard was observed.

d. Watershed Runoff Potential. The watershed is essentially rural with flat to mildly sloping terrain.

7. DOWNSTREAM CHANNEL

The channels below the northerly and southerly dams are narrow with a slope of about 0.7 percent. See Photographs 5 and 7. Both streambeds are composed primarily of gravel and cobbles. Located about 100 feet downstream of the southerly dam is an 8.8 foot wide by

11.8 foot high culvert beneath a road. This culvert appears to restrict the channel and is the hydraulic control during flood flow. The north channel is littered with debris, including two fallen trees. The two channels join as they enter Orange Lake about 1500 feet downstream of the dams.

8. OPERATION AND MAINTENANCE FEATURES

- a. Maintenance. Based on the observations made and information reported by a local resident, no maintenance has been performed on the dam in the past 10 years. It was reported that the southerly dam was breached approximately 10 years ago.

APPENDIX B

ENGINEERING DATA


This appendix lists the engineering data collected either from project records or other sources of data developed as a result of the visual inspection. The contents of this appendix are listed below.

<u>Appendix</u>	<u>Description</u>
B-1	General Project Data

APPENDIX B-1

GENERAL PROJECT DATA

The following plan, profile and cross-sections of the dams were developed from a limited stadia survey performed during visual inspection, field notes taken by inspection team members, and photographs taken during the visual inspection. The survey was referenced to an arbitrary local datum. Approximate U.S.G.S. elevations were obtained by noting the dam's location on the Gardner Lake, Maine U.S. Geologic Survey quadrangle and assuming that the spillway crest of the northerly dam to be equal to normal water surface of approximate elevation 90 (MSL).



NOT TO SCALE



B-1.2

2079915

EDWARD C. JORDAN CO., INC. PORTLAND, MAINE		U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS BALTIMORE, MARYLAND	
NATIONAL PROGRAM OF INSPECTION OF NON-FED. DAMS			
ROCKY LAKE DAMS			
GENERAL SITE SKETCH			
ORANGE RIVER		MAINE	
		SCALE	
		DATE MARCH 1979	

2079915


B-1.3




EDWARD C. JOHNSON CO., INC.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	
ROCKY LAKE DAMS	
SOUTHERLY DAM	
PLAN AND PROFILE	
ORANGE RIVER	
MAINE	
DATE	MARCH 1979

2079915

B-1.4






PLAN




DOWNSTREAM PROFILE

EDWARD C. JOHNSON & CO., INC.
 135 NORTH STREET, SUITE 100
 BOSTON, MASS. 02111
 NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS
 ROCKY LAKE DAMS
 NORTHERLY DAM
 PLAN AND PROFILE
 ORANGE RIVER
 MAINE
 DATE: MARCH 1977




B-1.5

EDWARD C. JORDAN CO., INC. PORTLAND, MAINE		U.S. ARMY ENGINEER DISTRICT OFFICE CONCORD, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
ROCKY LAKE DAMS			
NORTHERLY DAM			
X-SECTIONS			
ORANGE RIVER		MAINE	
DATE MARCH 1979		SCALE	



SECTION C



SECTION D

0 5 10 15 FEET

2079915

B-1.6

EDWARD C. JORDAN CO., INC. PORTLAND, MAINE		U.S. ARMY ENGINEER DIVISION NEW ENGLAND CORPS OF ENGINEERS BOSTON, MASS.	
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS			
ROCKY LAKE DAMS			
NORTHERLY DAM			
X-SECTIONS			
ORANGE RIVER		MAINE	
SCALE		DATE MARCH 1979	

APPENDIX C

PHOTOGRAPHS

The following are photographs referenced in this report.
See Sheet B-1 for photograph locations and orientations.



1

SOUTH DAM - DOWNSTREAM FACE



2

NORTH DAM - DOWNSTREAM FACE



3

UPSTREAM CHANNEL



4

SOUTH DAM - EARTH DIKE UPSTREAM



5

SOUTH DAM - DOWNSTREAM CHANNEL



6

SOUTH DAM - UPSTREAM CONTROL




7

NORTH DAM - DOWNSTREAM CHANNEL

APPENDIX D

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

Hydrologic computations pertinent to this investigation are attached. The following Location and Drainage area map shows the Rocky Lake watershed at the Rocky Lake Dams.




U.S. GEOLOGICAL SURVEY MAP
GARDNER LAKE, ME. QUADRANGLE
EASTPORT, ME. QUADRANGLE

0 1 2 3 MILES

EDWARD G. JORDAN CO., INC. PORTLAND, MAINE	U.S. ARMY ENGINEER DIV. NEW ENGLAND CORPS OF ENGINEERS WALTHAM, MASS.
NATIONAL PROGRAM OF INSPECTION OF NON-FED DAMS	
ROCKY LAKE DAMS	
LOCATION & DRAINAGE AREA MAP	
ROCKY LAKE	ME.
20759115	SCALE AS SHOWN DATE MARCH 1979

PROJECT
STORAGE DISCHARGE RATING CURVE
FOR NORTH AND SOUTH DAMS

COMP BY RTE	JOB NO. 20779 15
CHK BY JOD	DATE 3-22-79



D-3

Rocky Lake Dam

PROJECT AREAS ROCKY LAKE DAMS	COMP BY BTB	JOB NO. 20799 15
	CHK BY JJD	DATE 2-5-79

ITEM	AREA Measured from VSES Quads In ²	AREA Mi ²	AREA Acres
Rocky Lake D.A.	16.8	16.8	10752
Rocky Lake @ EL 90	1.80	1.80	1152
Rocky Lake @ EL 100	3.43	3.43	2195
Rocky Lake @ EL 120	6.08	6.08	3891
Orange Lake @ EL 76	0.38	0.38	243
Orange Lake @ EL 80	0.66	0.66	422
Orange Lake @ EL 100	1.16	1.16	742

FROM COE INVENTORY OF DAMS:

Normal Impounding Capacity = 6510 Ac-Ft
Maximum " " " = 7440 Ac-Ft

Normal Capacity seems reasonable.

Maximum Capacity @ Top of Dam
(@ EL 92):

$$6510 + 2 \left[1152 + \left(2195 - 1152 \right) \left(\frac{2}{10} \right) \left(\frac{1}{2} \right) \right] = \underline{9020 \text{ Ac-Ft}} \leftarrow \checkmark$$

To be used for
max. capacity

PROJECT ROCKY LAKE DAMS HYDRAULICS	COMP BY BTE	JOB NO. 20799 15
	CHK BY JSD	DATE 1-31-79

WEIR

DESIGNATION

LENGTH

C

North Dam

95

varies ←

North Dam Spillway

54

"

South Dam Road¹

63

"

¹ South Dam is breached. Any weir flow at the South Dam site would be over the roadway just downstream of the dam.

5-40

HANDBOOK OF HYDRAULICS

KING & KRATER

Table 5-3. Values of C in the Formula $Q = CLH^{3/2}$ for Broad-crested Weirs

Measured head in feet, H	Breadth of crest of weir in feet											
	0.50	0.75	1.00	1.50	2.00	2.50	3.00	4.00	5.00	10.00	15.00	
0.2	2.80	2.75	2.69	2.62	2.54	2.48	2.44	2.38	2.34	2.49	2.68	
0.4	2.92	2.80	2.72	2.64	2.61	2.60	2.58	2.54	2.50	2.56	2.70	
0.6	3.08	2.89	2.75	2.64	2.61	2.60	2.68	2.69	2.70	2.70	2.70	
0.8	3.30	3.04	2.85	2.68	2.60	2.60	2.67	2.68	2.68	2.69	2.64	
1.0	3.32	3.14	2.98	2.75	2.66	2.64	2.65	2.67	2.68	2.68	2.63	
1.2	3.32	3.20	3.08	2.86	2.70	2.65	2.64	2.67	2.68	2.69	2.64	
1.4	3.32	3.26	3.20	2.92	2.77	2.68	2.64	2.65	2.65	2.67	2.64	
1.6	3.32	3.29	3.28	3.07	2.89	2.75	2.68	2.66	2.65	2.64	2.63	
1.8	3.32	3.32	3.31	3.07	2.88	2.74	2.68	2.66	2.65	2.64	2.63	
2.0	3.32	3.31	3.30	3.03	2.85	2.76	2.72	2.68	2.65	2.64	2.63	
2.5	3.32	3.32	3.31	3.28	3.07	2.89	2.81	2.72	2.67	2.64	2.63	
3.0	3.32	3.32	3.32	3.32	3.20	3.05	2.92	2.73	2.66	2.64	2.63	
3.5	3.32	3.32	3.32	3.32	3.32	3.19	2.97	2.76	2.68	2.64	2.63	
4.0	3.32	3.32	3.32	3.32	3.32	3.32	3.07	2.79	2.70	2.64	2.63	
4.5	3.32	3.32	3.32	3.32	3.32	3.32	3.32	2.68	2.74	2.64	2.63	
5.0	3.32	3.32	3.32	3.32	3.32	3.32	3.32	3.07	2.79	2.64	2.63	
5.5	3.32	3.32	3.32	3.32	3.32	3.32	3.32	3.32	2.68	2.64	2.63	

PROJECT ROCKY LAKE DAM HYDRAULICS NORTH DAM	COMP BY	JOB NO.
	BTB	20799 15
	CHK BY JSD	DATE 1-31-79

MSL DATUM ELEV	Spillway HEAD feet	Spillway Q CFS	Dam HEAD feet	DAM Q CFS	TOTAL NORTH DAM Q, CFS
90	0	—		—	
	1	143		—	143
92	2	403	0	—	403
	3	741	1	250	991
94	4	1140	2	707	1847
	5	1594	3	1298	2892
96	6	2095	4	1999	4094
	7	2640	5	2793	5433
98	8	3226	6	3672	6898
	9	3849	7	4627	8476
100	10	4508	8	5653	10161
	11	5201	9	6746	11947
102	12	5926	10	7901	13827
	13	6682	11	9115	15797
104	14	7468	12	10386	17854
	15	8282	13	11711	19993
106	16	9124	14	13088	22212
	17	9992	15	14515	24507
108	18	10887	16	15990	26877
	19	11807	17	17513	29320
110	20	12751	18	19080	31831

PROJECT ROCKY LAKE DAM HYDRAULICS SOUTH DAM	COMP BY LTB	JOB NO. 20799 15
	CHK BY JSD	DATE 2-2-79

$$A = 817 \text{ ft}^2$$

$$Q = CA\sqrt{2gh}, C = 2.7$$

MSL DATUM ELEV	CULVERT AREA ft ²	CULVERT FLOW ¹ CFS	ROADWAY WEIR Q CFS	TOTAL SOUTH DAM FLOW
79		-	-	-
80	2.8	35		35
82	18.1	102		102
84	34.3	193		193
86	50.5	284		284
88	66.1	371		371
90	77.4	435		403
92	81.7	459		435
94			27	447
96			246	459
98			578	459
			993	486
			1477	705
100			2022	1037
102			2620	1452
104			3268	1936
106			3962	2481
108			4699	3079
110			5477	3727
			6294	4421
			7147	5158
			8037	5936
			8960	6753
			9916	7606
			10904	8496
				9419
				10375
				11363

¹ Since no backwater information was disclosed for stream, head through culvert was assumed to be 1.0 foot.

PROJECT STORAGE - DISCHARGE TABLE	COMP BY BTB	JOB NO. 2079915
	CHK BY JSD	DATE 2-5-79

MSL DATUM ELEV	TOTAL FLOW CFS	STORAGE ¹ ACRE-FT
----------------------	----------------------	---------------------------------

88	371	4206
	403	5358
90	435	6510
	590	7714
92	862	9023
	1450	10435
94	2333	11952
	3597	13574
96	5131	15299
	6855	17129
98	8834	19064
	10957	21102
100	13240	23245
	15674	25525
102	18248	27974
	20955	30593
104	23790	33322
	26746	36340
106	29818	39468
	33003	42765
108	36296	46232
	39695	49869
110	43194	53675

¹ Normal Water surface taken as EL FF.

PROJECT PMF CALCULATION	COMP BY BTB	JOB NO. 20799 15
	CHK BY JJD	DATE 2-5-79

According to "PRELIMINARY GUIDANCE FOR ESTIMATING MAX PROBABLE DISCHARGE" by COE:

For Flat D.A = 16.8 Sq M., $Q = 650 \text{ CSM}$

$$Q = 650 (16.8) = 10920 \text{ CFS} = \text{PMF}$$

$$5460 \text{ CFS} = \frac{1}{2} \text{ PMF}$$

ESTIMATING EFFECT OF SURCHARGE STORAGE:

$$Q_{p2} = Q_{p1} \times \left(1 - \frac{\text{STOR}_1}{\text{Runoff}}\right)$$

$$\text{PMF Runoff} = 19'' ; \frac{1}{2} \text{ PMF Runoff} = 9.5''$$

$$\text{Elev. to pass } Q_{p2} (\text{PMF}) = \underline{79.0'}$$

$$\text{STOR}_1 = 21102 - 4206 = 16896 \text{ Ac.-Ft}$$

$$\text{OR } \frac{16896}{10752} \times \frac{12 \text{ in}}{\text{ft}} = 18.86''$$

$$Q_{p2} = 10920 \left(1 - \frac{18.86}{19}\right) = 82$$

$$\text{STOR}_2 \approx 0$$

$$Q_{p3} = 10920 \left(1 - \frac{(18.86 + 0)/2}{19}\right) = 5500$$

$$\text{Elev. to pass } Q_{p3} = \underline{96.2}$$

PROJECT PMF CALCULATION	COMP BY BTB	JOB NO. 2079915
	CHK BY STD	DATE 2-5-79

$$STOR_3 = 15683 - 4206 = 11477 \text{ Ac-Ft}$$

$$\text{OR } \frac{11477}{10752} \times 12 = 12.81"$$

$$STOR_{AVE} = \frac{12.81 + 9.43}{2} = 11.12$$

$$Q_{p4} = 10920 \left(1 - \frac{11.12}{19} \right) = 4529$$

$$\text{Elev. to pass } Q_{p4} = 95.6$$

$$STOR_4 = 14622 - 4206 = 10416 \text{ Ac-Ft}$$

$$\text{OR } \frac{10416}{10752} \times 12 = 11.63$$

$$STOR_{AVE} = \frac{11.63 + 11.12}{2} = 11.37$$

$$Q_{p5} = 10920 \left(1 - \frac{11.37}{19} \right) = \underline{\underline{4384 \text{ cfs}}}$$

$$\text{Elev. to pass } Q_{p5} = \underline{\underline{95.5'}}$$

PROJECT V_2 PMF	COMP BY BTL	JOB NO. 20799 15
	CHK BY JJD	DATE 2-5-79

Elev. to pass Q_{p1} (V_2 PMF) = 5460 cfs
is 96.2'.

$$STOR_1 = 15643 - 4206 = 11436 \text{ Ac-Ft}$$

$$\text{OR } \frac{11436}{10752} \times 12 \frac{\text{in}}{\text{ft}} = 12.76''$$

$$Q_{p2} = 5460 \left(1 - \frac{12.76}{9.5} \right) < 0$$

$$\therefore STOR_2 = 0, \quad \text{STOR}_{AVE} = \frac{12.76}{2} = 6.38''$$

$$Q_{p3} = 5460 \left(1 - \frac{6.38}{9.5} \right) = 1793 \text{ cfs}$$

Elev. to pass Q_{p3} = 93.4

$$STOR_3 = 11025 - 4206 = 6819 \text{ Ac-Ft}$$

$$\text{OR } \frac{6819}{10752} \times 12 = 7.61''$$

$$STOR_{AVE} = \frac{7.61 + 6.38}{2} = 7.00''$$

$$Q_{p4} = 5460 \left(1 - \frac{7.00}{9.5} \right) = 1440 \text{ cfs}$$

Elev. to pass Q_{p4} = 93.0

$$STOR_4 = 10435 - 4206 = 6229 \text{ Ac-Ft}$$

$$\text{OR } \frac{6229}{10752} \times 12 = 6.95''$$

$$STOR_{AVE} = \frac{6.95 + 7.00}{2} = 6.98''$$

$$Q_{p5} = 5460 \left(1 - \frac{6.98}{9.5} \right) = 1450 \text{ cfs}$$

@ EL 93.0

PROJECT Dam Failure Hydrographs	COMP BY BTB	JOB NO. 20799 15
	CHK BY JSD	DATE 2-1-79

$$Q_{p1} = 8/27 W_b \sqrt{g} Y_o^{3/2}$$

$$1/2 Q_p T = 12.1 S$$

North Dam is most susceptible to failure.

$$\therefore W_b = 0.4 (149) = 59.6$$

$$Y_o = 14'$$

$$Q_{p1} = 8/27 (59.6) \sqrt{g} (14)^{3/2} = 5249$$

Top of Dam @ EL 92

Additional Flow in Orange River
would be from culvert flow at
South Dam = 459 cfs


$$\text{Total Failure Flow}^1 \approx \underline{\underline{5700 \text{ cfs}}}$$

$$\text{Storage} = S = 9020 \text{ Ac-Ft}$$

$$T = \frac{12.1 (9020)}{1/2 (5700)} = \underline{\underline{38.3 \text{ hrs.}}}$$

¹ Failure is assumed to occur through the spillway section. Therefore, no additional flow is added to the total failure flow for spillway discharge.

PROJECT STORAGE - DISCHARGE @ OUTLET OF ORANGE LAKE	COMP BY BTB	JOB NO. 2079915
	CHK BY JSD	DATE 2-6-79

COMPOSITE $n = 0.00$ 

$$\text{Slope} = \frac{76 - 60}{4.3 \times 5280} = 0.0007$$

<u>ELEV</u>	<u>Area, A_c</u> <u>STORAGE</u>	<u>A_c-FT</u> <u>STORAGE</u>	<u>$Q = 1.486 A R^{2/3} S^{1/2}$</u> <u>DISCHARGE, CFS</u>
76	243	—	—
80	422	1330	1180
81	438	1702	2175
82	454	2091	3452
83	470	2496	5014
84	486	2916	6868
85	502	3352	9024
86	518		
87	534		
88	550		
89	566		
90	582	6350	24768
100	742		

PROJECT Dam Failure Hydrographs	COMP BY BTB	JOB NO. 20799 15
	CHK BY JJD	DATE 2-6-79

$Q_{p2} = 5700 \text{ cfs}$
 AT OUTLET OF ORANGE POND:
 $Q_{p2} @ \text{EL } 83.4$
 $V_2 = 2651 \text{ AC-Ft}$

$$Q_{p2} (\text{TRIAL}) = Q_{p2} \left(1 - \frac{V_1}{S}\right)$$

$$Q_{p2} (\text{TRIAL}) = 5700 \left(1 - \frac{2651}{9020}\right) = 4025 \text{ cfs}$$

$$Q_{p2} (\text{TRIAL}) @ \text{EL } 82.4, V_2 = 2240 \text{ AC-Ft}$$

$$Q_{p2} = 5700 \left(1 - \frac{(2651 + 2240)/2}{9020}\right) = \underline{\underline{4155 \text{ cfs}}}$$

@ EL 82.4'


OR Approx. 6.4'
above normal pond
Elevation.

$$T = \frac{12.1 (9020)}{V_2 (4155)} = 52.5 \text{ hrs.}$$

PROJECT	STORAGE - DISCHARGE AT FIRST BRIDGE BELOW ORANGE LAKE	COMP BY	JOB NO.
		BTB	2079915
		CHK BY	DATE
		JJD	2-6-79

Composite $n = 0.06$

X-Section Near Bridge
Location



Slope = 0.0007

ELEV	Area, A _c STORAGE	Ac-Ft STORAGE
67	—	—
	14	7
	28	28
70	41	62
	55	110
	69	172
	83	248
	96	337
75	110	441
	124	558
	138	688
	151	833
	165	991
80	179	1164

$$Q = \frac{1.486}{n} A R^{2/3} S^{1/2}$$

DISCHARGE, CFS

180

1669
2217
2863
3613
4473
5455

PROJECT Dam Failure Hydrographs	COMP BY BTB	JOB NO. 20799 15
	CHK BY JSD	DATE 2-6-79

$$Q_{p1} = 4155$$

AT BRIDGE 2.2 MILES DOWNSTREAM
OF DAM.

$$Q_{p2} @ EL 78.6'$$

$$V_1 = 933 A_c - Ft$$

$$Q_{p2} (TRIAL) = 4155 \left(1 - \frac{933}{9020}\right) = 3725 \text{ CFS}$$

$$Q_{p2} (TRIAL) @ EL 78.1', V_2 = 854 A_c - Ft$$

$$Q_{p2} = 3725 \left(1 - \frac{(933 + 854)/2}{9020}\right) = \underline{\underline{3356 \text{ CFS}}}$$


$$\underline{\underline{@ EL 77.7'}}$$

Downstream of this bridge the
failure hydrograph would be maintained
within the area designated as swamp
on the Eastport, ME USGS map.

$$T = \frac{12.1(9020)}{1/2(3356)} = \underline{\underline{65 \text{ hrs}}}$$

PROJECT DAM FAILURE HYDROGRAPH		
COMP BY BETZ	JOB NO. 20714 15	
CHK BY JJD	DATE 2-9-77	

Q_{p1} @ Dam
 Q_{p2} @ Outlet of Orange Lake
 Q_{p3} @ Bridge 2.2 miles below Dam



D-17

Rocky Lake Dam

PROJECT CLASSIFICATION	COMP BY BTP	JOB NO. 20799 15
	CHK BY JD	DATE 2-6-79

ACCORDING TO "RECOMMENDED
GUIDELINES FOR SAFETY INSPECTION
OF DAMS" :

Rocky Lake Dam is an intermediate
sized dam, Storage = 9020 Ac-Ft
Height = 14'

From Guidelines \rightarrow Storage ≥ 1000 and $\leq 50,000$
or Height ≥ 40 and < 100

Hazard Potential Classification:

LOW

\therefore Recommended Spillway design Flood
is 100yr to $\frac{1}{2}$ PMF.

USE $\frac{1}{2}$ PMF

Routed $\frac{1}{2}$ PMF = 1450 CFS @ EL 93.0

Capacity of dam at Top of Dam
EL 92 = 862 CFS

Spillway Capacity = 59% of $\frac{1}{2}$ PMF

APPENDIX E

Information as Contained in the National
Inventory of Dams



INVENTORY OF DAMS IN THE UNITED STATES

STATE	IDENTITY NUMBER	DIVISION	STATE	COUNTY	CONGR. DIST.	STATE	COUNTY	CONGR. DIST.	NAME	LATITUDE (NORTH)	LONGITUDE (WEST)	REPORT DATE DAY MO YR
NE	329	FED	NE	029	02				ROCKY LAKE DAM	4446.1	6715.9	22MAR79

POPULAR NAME	NAME OF IMPOUNDMENT
	ROCKY LAKE

REGION	BASE	RIVER OR STREAM	NEAREST DOWNSTREAM CITY-TOWN-VILLAGE	DIST FROM DAM (MI.)	POPULATION
01	01	ROCKY LAKE STREAM	WHITING	1	279

TYPE OF DAM	YEAR COMPLETED	PURPOSES	STRUCTURAL HEIGHT (FT.)	HYDRAULIC HEIGHT (FT.)	IMPOUNDING CAPACITIES	
					MAXIMUM (ACRE-FT.)	NORMAL (ACRE-FT.)
FRR		R	14	10	6510	4200

DIST OWN FED R PRV/FED SCS A VER/DATE

NED N N N N

REMARKS

D/S HAS	SPILLWAY			MAXIMUM DISCHARGE (FT.)	VOLUME OF DAM (CY)	POWER CAPACITY		NAVIGATION LOCKS									
	CREST LENGTH	TYPE	WIDTH (FT.)			INSTALLED (MW)	PROPOSED (MW)	NO.	LENGTH (FT.)	WIDTH (FT.)	LENGTH (FT.)	WIDTH (FT.)	LENGTH (FT.)	WIDTH (FT.)			
3	150	11	53	400													

OWNER	ENGINEERING BY	CONSTRUCTION BY
M. GARDNER + HERMAN GALVIN		

REGULATORY AGENCY			
DESIGN	CONSTRUCTION	OPERATION	MAINTENANCE
NONE	NONE	NONE	NONE

INSPECTION BY	INSPECTION DATE DAY MO YR	AUTHORITY FOR INSPECTION
EDWARD C. JORDAN CO. INC.	28NOV78	PUBLIC LAW 92-367 AUG1972

REMARKS